

FOREST ROAD EXCISE TAX SUMMARY SHEET

Region: Pacific Cascade

Timber Sale Name: Throw a Bone

Application Number: 30-076144

Excise Tax Applicable Activities

Construction: _____ linear feet
Road to be constructed (optional and required) but not abandoned

Reconstruction: 18,645 linear feet
Road to be reconstructed (optional and required) but not abandoned

Abandonment: _____ linear feet
Abandonment of existing roads not reconstructed under the contract

Deactivation: _____ linear feet
Road to be made undriveable but not officially abandoned.

Pre-Haul Maintenance: 749 linear feet
Existing road to receive maintenance work (specifically required by the contract) prior to haul

Excise Tax Exempt Activities

Temporary Optional Construction: _____ linear feet
Optional roads to be constructed and then abandoned

Temporary Optional Reconstruction: _____ linear feet
Optional roads to be reconstructed and then abandoned

New Abandonment: _____ linear feet
Abandonment of roads constructed or reconstructed under the contract

STATE OF WASHINGTON
DEPARTMENT OF NATURAL RESOURCES
PACIFIC CASCADE REGION

THROW A BONE

ROAD PLAN

SECTION 2, 11, 13, 14, TOWNSHIP 10 NORTH, RANGE 08 WEST, W.M.
WAHIAKUM COUNTY

PACIFIC DISTRICT

AGREEMENT NO.: 30-076144

CONTRACT ADMINISTRATOR: Larry Leach

DATE: 03/01/2004

STAFF ENGINEER: Charlie Hanlin

DRAWN & COMPILED BY: Alicia Compton

SECTION 0 – SCOPE OF PROJECT

This project includes but is not limited to construction including:

landing construction.

This project also includes reconstruction including:

pulling ditches;
cleaning ditches;
acquisition and installation of additional drainage structures;
grading and shaping existing road surface and turnouts;
constructing additional turnouts;
acquisition and application of rock;
grass seeding.

This project also includes pre-haul maintenance including:

cleaning ditches.

SECTION 1 - GENERAL CLAUSES

1.1-1

Clauses in this plan apply to all construction or reconstruction including landings unless otherwise noted.

1.1-2

Reconstruction of the following roads is required. All roads shall be reconstructed on the State's location and in accordance with this Road Plan.

<u>Road</u>	<u>Stations</u>	<u>Type</u>
G-2100	0+00 to 157+95	Reconstruction
G-2180	0+00 to 23+50	Reconstruction
G-2180 Shoefly	0+00 to 5+00	Reconstruction
Spur 1	0+00 to 7+49	Pre-haul maintenance

1.1-4

If the Purchaser desires a road location or design change, a revised Road Plan shall be submitted to the State for consideration.

1.1-5

On this plan quantities are minimum acceptable values. Additional quantities required by the State because of hidden conditions or Purchaser's choice of construction season or techniques shall be at the Purchaser's expense. Hidden conditions include, but are not limited to: solid subsurface rock, subsurface springs, saturated ground, and unstable soil.

1.1-7

Hauling of forest products or equipment may require a county road hauling permit. Purchaser is responsible for obtaining a permit, and any costs associated with extra maintenance or repair levied by a county.

1.2-1

The reconstruction of any roads specified herein shall not be permitted between September 30 and May 1 unless authority to do so is granted, in writing, by the Contract Administrator.

1.2-2

Purchaser shall not use roads reconstructed under this Road Plan for hauling, other than timber cut on the right-of-way, without written approval from the Contract Administrator.

1.3-2

Roads are intended for dry weather use. Hauling shall be suspended when wheel track rutting exceeds 6 inches unless Purchaser elects to correct the situation at his/her own expense. Corrective measures and continued operations are subject to written approval by the Contract Administrator.

1.4-3

Reference points (R.P.'s) that are moved or damaged at any time during construction shall be reset in their original locations by the Purchaser. Excavation and embankment shall not proceed on road segments controlled by said R.P.'s until all moved or damaged R.P.'s are reset.

1.5-1

Maintenance on roads listed in Contract Clauses C-50 (Purchaser Road Maintenance and Repair) and C-60 (Designated Road Maintainer) shall be performed in accordance with Forest Access Road Maintenance Specifications.

SECTION 4 - DEBRIS DISPOSAL AND REMOVAL

4.1-1

Right-of-way debris is defined as all nonmerchantable vegetative material larger than one cubic foot in volume, within the grubbing limits.

4.1-2

All right-of-way debris disposal shall be completed prior to the application of rock or timber haul.

4.2.3-1

Right-of-way debris shall be scattered.

4.2.3-3

Right-of-way debris shall not be placed against standing timber.

SECTION 5 - EXCAVATION

5.1-1

Roads shall be reconstructed in accordance with dimensions shown on the TYPICAL SECTION SHEET.

5.1-7

Roads shall be reconstructed to the dimensions shown on the TYPICAL SECTION SHEET, within the tolerance listed below. Tolerance classes for each road are listed on the TYPICAL SECTION SHEET.

<u>Tolerance Class</u>	<u>A</u>	<u>B</u>	<u>C</u>
Road Width (feet)	+1.5	+1.5	+2.0
Subgrade elevation (feet +/-)	0.5	1.0	2.0
Centerline alignment (feet lt./rt.)	1.0	1.5	3.0

5.1-8

Excavation slopes shall be constructed no steeper than shown on the following table:

<u>Material Type</u>	<u>Excavation Slope Ratio</u>
Common Earth (on side slopes of 55%)	1:1
Common Earth (55% to 70% sideslopes)	$\frac{3}{4}$:1
Common Earth (on slopes over 70%)	$\frac{1}{2}$:1
Fractured or loose rock.....	$\frac{1}{2}$:1
Hardpan or solid rock.....	$\frac{1}{4}$:1

5.1-11

Embankment slopes shall be constructed no steeper than shown on the following table:

<u>Material Type</u>	<u>Embankment Slope Ratio</u>
Common Earth and Rounded Gravel.....	$1\frac{1}{2}$:1
Angular Rock.....	$1\frac{1}{4}$:1
Sandy Soils	2:1

5.1-12

Organic material shall be excluded from embankment as shown on the TYPICAL SECTION SHEET.

5.1-16

Turnout locations noted on this plan are approximate. Locations shall be adjusted to fit with final subgrade alignment and sight distances. Location shall be subject to written approval of the Contract Administrator.

5.1.1-2

Waste material shall not be deposited within 100 feet of a live stream.

5.1.1-7

On the following road, all excess excavated material shall be end hauled to designated waste areas.

End Haul/Waste Material Disposal

<u>Road</u>	<u>Stations</u>	<u>Waste Area Location</u>
G-2100	Culvert replacement locations	As designated by the Contract Administrator

5.1.1-8

The amount of material to be contained in a waste area shall be at the discretion of the Contract Administrator.

5.1.2-1

Select borrow shall contain no more than 5% dirt, vegetative debris, or other waste material by volume.

5.1.2-2

Select borrow shall be used at the following locations:

<u>Road</u>	<u>Stations</u>
G-2100	All culvert replacements

5.1.2-3

Select borrow may be obtained from any commercial source as approved by the Contract Administrator.

5.3-1

All embankment and waste material shall be compacted. The minimum acceptable compaction is achieved by placing embankments in 2 foot or shallower lifts and routing excavation equipment over entire width of the lifts.

5.4-1

Silt-bearing runoff shall not be permitted to go into streams.

5.4-3.1

On the following roads, Purchaser shall furnish and evenly spread the seed mixture listed below on all exposed soil inside the grubbing limits at a rate of 50 pounds per acre. The date of application is subject to approval by the Contract Administrator.

<u>Mixture Percent by Weight</u>	<u>Minimum Percent Germination</u>
50% Fescue, Red	90% Germination
25% Ryegrass, Perennial	90% Germination
15% Bentgrass	85% Germination
10% Clover, White and White Dutch (inoculated)	90% Germination

Weed seed shall not exceed 0.5% by weight.

Seed shall be furnished in standard containers on which the following shall be shown:

1. Common name of seed
2. Net weight
3. Percent of purity
4. Percentage of germination
5. Percentage of weed seed and inert material

Required seed not spread by the termination of this contract shall become property of the State.

<u>Road</u>	<u>Stations</u>	<u>Seed Quantity</u> <u>(lbs)</u>
G-2100	Culvert replacement locations	10

SECTION 6 - DRAINAGE

6.2.1-1

Purchaser shall furnish, install, and maintain corrugated polyethylene pipe (AASHTO specification No. M-294 Type S) as designated on the CULVERT LIST. Culvert and flume lengths shall be varied to fit as-built conditions subject to written approval by the Contract Administrator.

6.2.1-2

Manufacturer's approved connectors shall be used for corrugated polyethylene pipe.

6.2.1-5

On required roads: culverts, downspouts, flumes, bands, and gaskets as listed on the CULVERT LIST which are not installed shall become property of the State.

6.2.2.1-1

Culvert, downspout, flume, and energy dissipator installation shall be in accordance with CULVERT AND DRAINAGE SPECIFICATION DETAIL and the Corrugated Polyethylene Pipe Association "Recommended Installation Practices for Corrugated Polyethylene Pipe and Fittings."

6.2.2.3-1

Cross drains and surface culverts on road grades in excess of 3% shall be skewed at least 30 degrees from perpendicular to the road centerline, except that cross drain culverts at the low points of dips in roads shall not be skewed.

6.2.2.3-2

Cross drain culverts shall be installed at a slope steeper than the incoming ditch grade, but not less than 3% nor more than 10%.

6.2.2.4-1
Installations of polyethylene tubing shall be subject to written approval of the Contract Administrator prior to making backfill.

6.2.2.5-1
Drainage structure outfalls shall not terminate directly on unprotected soil that will erode. Downspouts, flumes, and energy dissipators shall be installed to prevent erosion.

6.3-2
On the following roads, the Purchaser shall pull the ditches, reshape all culvert headwalls and catch basins, and clean the inlet and outlet of all culverts. Work shall be completed prior to application of rock and/or timber haul and shall be done in accordance with the TYPICAL SECTION SHEET and CULVERT AND DRAINAGE SPECIFICATION DETAIL.

<u>Road</u>	<u>Stations</u>
G-2100	74+95 to 157+95
G-2180	0+00 to 23+50
G-2180 Shoefly	0+00 to 5+00

6.4-1
Catch basins shall be constructed to resist erosion in accordance with CULVERT AND DRAINAGE SPECIFICATION DETAIL. Minimum dimensions: two feet wide and four feet long with backslopes consistent with Clause 5.1-8: Excavation Slopes.

SECTION 7 - ROCK

7.1-6
Rock for reconstruction under this contract may be obtained from any commercial source as approved in writing by the Contract Administrator.

<u>Possible Source</u>	<u>Location</u>
Naselle Rock	Naselle, Washington

7.2.1.1-6
3 INCH MINUS CRUSHED ROCK

% passing 3" square sieve.....	100%
% passing 2" square sieve.....	65 - 95%
% passing ¾" square sieve	28 - 70%
% passing ¼" square sieve.....	10 - 35%
% passing U.S. #200 sieve.....	0 - 10%

All percentages are by weight.

7.2.1.1-12
Landing rock shall be no coarser than 6 INCH MINUS.

7.2.3-4
Measurement of the 3 INCH MINUS CRUSHED rock shall be accomplished with State certified platform scales provided by the Purchaser and meeting the following specifications:

- a. The scales shall have an enclosed weatherproof room around the reading device.
- b. The weighing mechanism shall contain a weight totalizer and ticket imprinter. A ticket for each truck shall be made and delivered to the Contract Administrator.
- c. The totalizer calibration adjustment and ticket imprinter shall be furnished with a hasp to accept a State padlock.

7.4.2-1

Apply at least the minimum required rock quantity as shown on the ROCK LIST. Required rock shall meet the specifications on the ROCK LIST.

7.4.2-6

A grader shall be used to shape the existing surface prior to timber haul.

<u>Road</u>	<u>Stations</u>
G-2100	0+00 to 157+95
G-2180 Shoefly	0+00 to 5+00

7.4.2-9

Turnouts shall have rock applied to the same depth and specifications as the traveled way.

7.4.2-11

Purchaser shall spot patch as directed by the Contract Administrator in accordance with quantities shown on ROCK LIST.

SECTION 8 - STRUCTURES

8.4-8

During periods of hauling, Purchaser shall keep gates closed except for passing vehicles.

SECTION 9 - ROAD AND LANDING DEACTIVATION

9.2-1

Purchaser shall reduce or relocate landing debris, in a manner approved, in writing, by the Contract Administrator, to avoid landing failures and potential debris slides.

9.2-2


Purchaser shall provide for drainage of the landing surface as approved, in writing, by the Contract Administrator.

9.2-3

Landing embankments shall be sloped to original construction specifications.

Page 7 of 13

ROCK LIST




BALLAST

Road Number	From Station	To Station	Rock Slope	Compacted Rock Depth	C.Y./ Station	# of Stations	C.Y. Subtotal	Rock Source	Turnout		
									Length	Width	Taper
			K2	B2					L	H	T
G-2100 G-2100	Turnouts (7) Spot rock		2:1	9"	3 INCH MINUS CRUSHED		147 600	Any commercial source	100'	10'	25'


3 INCH MINUS CRUSHED TOTAL 747 Cubic Yards

THROW A BONE ROAD PLAN MAP



CULVERT LIST


Road Number	Location	Culvert		Length (ft)			Riprap (C.Y.)			Backfill Material	Placement Method	Const. Staked	Remarks
		Dia.	Gauge	Culvert	Downspt	Flume	Inlet	Outlet	Type				
			If										
G-2100	84+00	18"	-	36	-	-	-	-	-	SB	-	-	Replace existing
	94+75	18"	-	38	-	-	-	-	-	SB	-	-	Replace existing
	96+65	18"	-	40	-	-	-	-	-	SB	-	-	Replace existing
			Steel										




- Key:
- SB - Select Borrow
 - NT - Native (bank run)
 - SL - Select Fill
 - HL - Heavy Loose Riprap
 - LL - Light Loose Riprap
 - Flume - Half round pipe
 - Downspout - Full round pipe

CULVERT AND DRAINAGE SPECIFICATION DETAIL

(Page 1 of 2)



Proper preparation of foundation and placement of bedding material shall precede the installation of all culvert pipe. This includes necessary leveling of the native trench bottom and compaction of required bedding material to form a uniform dense unyielding base. The backfill material shall be placed so that the pipe is uniformly supported along the barrel.



Headwalls to be constructed of material that will resist erosion.

Dissipator Specifications:
Depth: 1 culvert diameter
Aggregate: as specified in the CULVERT LIST.


CULVERT AND DRAINAGE SPECIFICATION DETAIL

(Page 2 of 2)

POLYETHYLENE PIPE INSTALLATION

INSTALLATION REQUIREMENTS:

- 1. Crushed stone, gravel, or compacted soil backfill material shall be used as the bedding and envelope material around the culvert. The aggregate size shall not exceed 1/6 pipe diameter or 4" diameter, whichever is smaller.
- 2. The corrugated pipe shall be laid on grade, on a layer of bedding material as shown for the two types of installations. If native soil is used as the bedding and backfill material, it shall be well compacted in six inch layers under the haunches, around the sides and above the pipe to the recommended minimum height of cover.
- 3. Either crushed aggregate or flexible (asphalt) pavement may be laid as part of the minimum cover requirements.
- 4. Site conditions and availability of bedding materials often dictate the type of installation method used.
- 5. The load bearing capability of flexible conduits is dependent on the type of backfill material used and the degree of compaction achieved. Crushed stone and gravel backfill materials typically reach a compaction level of 90-95% AASHTO standard density without compaction. When native soils are used as backfill material, a compaction level of 85% is required. This minimum compaction can be achieved by either hand or mechanical tamping.



MINIMUM DIMENSIONS
Trench or Open Ditch Installation

Nominal Diameter	Minimum Thickness	Minimum Cover	Min. Trench Width
D	B	C	W
18"	6"	12"	36"
24"	6"	12"	42"
30"	6"	12"	48"
36"	6"	12"	54"

STATE OF WASHINGTON
DEPARTMENT OF NATURAL RESOURCES

FOREST ACCESS ROAD
MAINTENANCE SPECIFICATIONS

1. CONSTRUCTION AND RECONSTRUCTION (Prior to acceptance to the contract or acceptance on a timber sale).

A. Cuts and Fills

1. Maintain slope lines as constructed. Remove slides from the ditches and roadway. Replace fills to 1½:1 slopes with selected material or as directed. Remove overhanging material from the cut slopes.
2. Material from slides or other sources requiring removal shall not be deposited in streams or at locations where it will erode into streams or water courses.
3. Undesirable slide materials and debris shall not be mixed into the surface material.

B. Surface

1. Grade and shape the road surface, turnouts, and shoulders to the original crown, inslope or outslope as directed to provide suitable traveled surface and surface water runoff in an even, unconcentrated manner.
2. Blading must not undercut the backslope at the bottom of the ditchline or cut geotextile at centerline.
3. Watering may be required to control dust and to retain fine surface rock.
4. Desirable surface material shall not be bladed off the roadway.
5. Replace surface material lost or worn away.
6. Remove berms except as directed by the State.
7. Barrel spread soft spots to prevent degradation of geotextile.

C. Drainage

1. Keep ditches and drainage channels at outlets and inlets of culverts clear of obstructions and functioning as intended.
2. Inspect and clean culverts at least monthly, with additional inspections during storms and periods of high runoff. This must be done even during periods of inactivity.
3. Add stable material at the outlet end of the culvert as needed to stabilize the stream bed.
4. Headwalls: maintain to the road shoulder level with material that will resist erosion.
5. Keep silt bearing surface runoff from getting into live streams.

D. Structures


Repair bridges, culverts, cattleguards, fences, and other road structures to the condition required by the construction specifications.

E. Termination of Use or End of Season

Do maintenance work to minimize damage from the elements such as blading to insure correct runoff, ditch, and culvert cleaning and water bars.

F. Debris

Remove fallen timber, limbs, and stumps from the slopes or roadway.



DEPARTMENT OF NATURAL RESOURCES - CENTRAL REGION

FORM 9-87(Rev. 12-02)

SUMMARY - Road Development Costs

DISTRICT: Pacific

SALE/PROJECT NAME: Throw a Bone

CONTRACT NUMBER: 30-076144

LEGAL DESCRIPTION: Sections2,5 Township10 North, Range8 West W.M.

ROAD NUMBER:	G2100	0	G2180,Spur 1, G2180 Shoefly
ROAD STANDARD:	Mainline (14' R.S.)	Secondary Mainline (12' R.S.)	Spur road (10' R.S.)
NUMBER OF STATIONS:	157.95	0.00	36.00
SIDESLOPE:	0	0	0
DITCHING:	\$4,739	\$0	\$3,191
EXCAVATION AND FILL:	\$0	\$0	\$0
ROCK TOTALS (Cu. Yds.):			
Ballast: 147	\$4,139	\$0	\$0
Surface: 600	\$9,300	\$0	\$0
Riprap: 0	\$0	\$0	\$0
CULVERTS AND FLUMES:	\$1,375	\$0	\$0
STRUCTURES:	\$0	\$0	\$0
GENERAL EXPENSES:	\$1,955	\$0	\$383
MOBILIZATION:	\$575	\$0	\$575
TOTAL COSTS:	\$22,082	\$0	\$4,149
COST PER STATION:	\$140	\$0	\$115
NOTE: This appraisal has no allowance for profit and risk.		TOTAL (All Roads) =	\$26,231
		SALE VOLUME MBF =	3,500
		TOTAL COST PER MBF =	\$7.49

Plans to be furnished by:	Compiled by: Hanlin	Date: 03/04/04
Plan only: STATE	Checked by:	Date:
Plan-profile:	Region Engineer:	Date:
	Div of Engr.:	Date:

REMARKS:

CENTRAL REGION - ROAD COST ESTIMATE

SALE NAME: Throw a Bone

CONTRACT NUMBER: 30-076144

I. CLEARING AND GRUBBING:

	Flat Rate -	% Side Slope	MBF/ac	Disposal Factor	Production Factor	Cost/ Station	Width Factor	Total Stations	Sub Total
G2100				1.00	1.00	\$30	1.00	157.95	\$4,739
									\$0
									\$0
									\$0
									\$0
Clear and Grub TOTAL =									\$4,739

II. DITCHING :

	Flat Rate -	% Side Slope	Exc. Type Fact.	Production Factor	Cost/ Station	Width Factor	Total Stations	Sub Total
G2100			1.00		\$88	1.00	157.95	\$0
							0.00	\$0
							0.00	\$0
							0.00	\$0
							0.00	\$0
End Haul, Over Haul, Large Fills/Cuts					Estimated Vol. (cy)	No. of Equip. Days	Cost/day	Sub Total
End Haul/ Over Haul Large Fills/ Cuts								\$0
								\$0
Excavation TOTAL =								\$0

III. BALLAST AND SURFACING :

Ballast source: Commercial Source
Surface source:
Riprap source :

Description		= cubic yards
Back fill (3"-)	1	147.00
Spot rock (3"-)	1	600.00
Riprap		

UNIT COSTS	Ballast	Surfacing	Riprap
Drill & Shoot	\$0.00	\$0.00	
Dig and load	\$0.00	\$0.00	
Crushing	\$0.00	\$0.00	
Purchase	\$7.00	\$7.00	
Haul *	\$7.25	\$7.25	\$7.25
Spread	\$0.80	\$0.80	
Compact	\$0.45	\$0.45	
Strip			
Reclamation			
TOTAL (\$/cy)	\$15.50	\$15.50	\$7.25

* Haul Formula: (R.T.Miles/MPH+Delay)(\$/hr / Cy/load)

R.T. Miles =	14.0				
Ave. Speed =	15	Back fill (3"-)	267 Cu. yds @	\$15.50 /cu. yd =	\$4,139
Delay (Hrs.)=	0.2	Spot rock (3"-)	600 Cu. yds @	\$15.50 /cu. yd =	\$9,300
Cost / Hour =	\$64.00	Riprap	0 Cu. yds @	\$7.25 /cu. yd =	\$0
CY / Load =	10				

Rock total = \$13,439

IV. CULVERTS AND FLUMES:

Description	Qty.	Gauge	Diameter	No/Length	Installed Cost/ft	Sub-total
CPP	1		18	36	\$11.80	\$425
	1		18	38	\$11.80	\$448
	1		18	40	\$11.80	\$472
Bands & Gaskets	3			1	\$9.90	\$30

Culvert total = \$1,375

V. STRUCTURES

Description	Type	Width	Length	Cost/ft.	Sub-total
					\$0
					\$0
					\$0

Structure total = \$0

Sub-TOTAL = \$19,552

VI. GENERAL EXPENSES:

Overhead & General Exp. Add 10% \$1,955

VII. MOBILIZATION:

Description	\$ per Move	# of Moves	Sub-total
Dump Trucks	100	3	\$300
Grader	400	1	\$400
* Move in costs are averaged over all three sheets.			\$0
Excavator	450	1	\$450
			\$0
			\$0
			\$0
			\$0

Total Mobilization = \$1,150 Mobilization sub-total = \$575

Road No. G2100
Standard: Mainline (14' R.S.)
Stations: 157.95

SHEET TOTAL = \$22,082

By: Hanlin

Sheet 2 of 4

Date: 03/04/04

CENTRAL REGION - ROAD COST ESTIMATE

SALE NAME: Throw a Bone

CONTRACT NUMBER: N/A

I. CLEARING AND GRUBBING:

	Flat Rate -	% Side Slope	MBF/ac	Disposal Factor	Production Factor	Cost/ Station	Width Factor	Total Stations	Sub Total
0		30%	35	1.00	3.90	\$40	1.00	0.00	\$0
		40%	35	1.00	4.29	\$40	1.00	0.00	\$0
		50%	35	1.00	4.70	\$40	1.00	0.00	\$0
		60%	35	1.00	6.15	\$40	1.00	0.00	\$0

Clear and Grub TOTAL = \$0

II. EXCAVATION:

	Flat Rate -	% Side Slope	Exc. Type Fact.	Production Factor	Cost/ Station	Width Factor	Total Stations	Sub Total
0		30%	1.00	2.50	\$88	1.00	0.00	\$0
		40%	1.00	4.56	\$88	1.00	0.00	\$0
		50%	1.00	6.85	\$88	1.00	0.00	\$0

*End Haul, Over Haul, Large Fills/Cuts	Estimated Vol. (cy)	No. of Equip. Days	Cost/day	Sub Total
End Haul/ Over Haul	5000	8	\$0	\$0
Large Fills/ Cuts	3000	5	\$0	\$0

Excavation TOTAL = \$0

III. BALLAST AND SURFACING :

Ballast source: commercial source
Surface source: commercial source
Riprap source : commercial source

Description	cu.yds/sta	x stations	= cubic yards
Ballast (4"-)	51	0.00	0
Surfacing (2 1/2"-)	30	0.00	0
Riprap			

UNIT COSTS	Ballast	Surfacing	Riprap
Drill & Shoot	\$2.50	\$2.50	
Dig and load	\$1.00	\$1.00	
Crushing	\$2.50	\$3.25	
Purchase			
Haul *	\$1.69	\$1.69	\$1.69
Spread	\$0.80	\$0.80	
Compact	\$0.45	\$0.45	
Strip			
Reclamation			
TOTAL (\$/cy)	\$8.94	\$9.69	\$1.69

* Haul Formula: (R.T.Miles/MPH+Delay)(\$/hr / Cy/load)

R.T. Miles =	6.0					
Ave. Speed =	25	Ballast (4"-)	0 Cu. yds @	\$8.94 /cu. yd =	\$0	
Delay (Hrs.)=	0.2	Surfacing (2 1/2"	0 Cu. yds @	\$9.69 /cu. yd =	\$0	
Cost / Hour =	\$77.00	Riprap	0 Cu. yds @	\$1.69 /cu. yd =	\$0	
CY / Load =	20					

Rock total = \$0

IV. CULVERTS AND FLUMES:

Description	Qty.	Gauge	Diameter (in.)	No/Length (ft)	Installed Cost/ft	Sub-total
	0	na	18	36	\$11.80	\$0
	0	14	24	50	\$16.70	\$0
	0	14	36	50	\$25.30	\$0

Bands & Gaskets 0 - 18"@ \$9.90ea,0 -24" @ \$13.20 ea,0 - 36" @ \$24.15 ea \$0

Culvert total = \$0

V. STRUCTURES

Description	Type	Width	Length	Cost/ft.	Sub-total
					\$0
					\$0
					\$0

Structure total = \$0

Sub-TOTAL = \$0

VI. GENERAL EXPENSES:

Overhead & General Exp. Add 12% \$0

VII. MOBILIZATION:

Description	\$ per Move	# of Moves	Sub-total
Dump Trucks	\$100	0	\$300
Grader	\$400	0	\$400
0	\$0	0	\$0
Excavator	\$450	0	\$450
0	\$0	0	\$0
0	\$0	0	\$0
0	\$0	0	\$0
0	\$0	0	\$0

Total Mobilization = \$1,150

Mobilization sub-total =

Road No. 0
Standard: Secondary Mainline (12' R.S.)
Stations: 0.00

SHEET TOTAL = \$0

By: Hanlin

Sheet 3 of 4

Date: 03/04/04

CENTRAL REGION - ROAD COST ESTIMATE

SALE NAME: Throw a Bone

CONTRACT NUMBER: 30-076144

I. CLEARING AND GRUBBING:

Flat Rate -	% Side Slope	MBF/ac	Disposal Factor	Production Factor	Cost/ Station	Width Factor	Total Stations	Sub Total
G2180,Spur 1, G2180 Shoefly	20%	35	1.00	2.77	\$32	1.00	36.00	\$3,191
	30%	35	1.00	3.90	\$32	0.80	0.00	\$0
	40%	35	1.00	4.29	\$32	0.80	0.00	\$0
	50%	35	1.00	4.70	\$32	0.80	0.00	\$0

Clear and Grub TOTAL = \$3,191

II. EXCAVATION:

Flat Rate -	% Side Slope	Exc. Type Fact.	Production Factor	Cost/ Station	Width Factor	Total Stations	Sub Total
G2180,Spur 1, G2180 Shoefly	20%	1.00	2.00	\$66	0.50	36.00	\$0
	30%	1.00	2.50	\$66	0.50	0.00	\$0
	40%	1.00	4.56	\$66	0.50	0.00	\$0
	50%	1.00	6.85	\$66	0.50	0.00	\$0

*End Haul, Over Haul, Large Fills/Cuts	Estimated Vol. (cy)	No. of Equip. Days	Cost/day	Sub Total
End Haul/ Over Haul	0	0	\$0	\$0
Large Fills/ Cuts	0	0	\$0	\$0

Excavation TOTAL = \$0

III. BALLAST AND SURFACING :

Ballast source:
Surface source:
Riprap source :

Description	cu.yds/sta x stations =	cubic yards
Ballast (4"-)	0 36.00	0
Surfacing (2 1/2"-)	0 36.00	0
Riprap		

UNIT COSTS	Ballast	Surfacing	Riprap
Drill & Shoot	\$2.50		
Dig and load	\$1.00		
Crushing	\$2.50		
Purchase			
Haul *	\$1.08	\$1.08	\$1.08
Spread	\$0.80		
Compact	\$0.45		
Strip			
Reclamation			
TOTAL (\$/cy)	\$8.33	\$1.08	\$1.08

* Haul Formula: (R.T.Miles/MPH+Delay)(\$/hr / Cy/load)

R.T. Miles =	2.0					
Ave. Speed =	25	Ballast (4"-)	0 Cu. yds @	\$8.33 /cu. yd =		\$0
Delay (Hrs.)=	0.2	Surfacing (2 1/2'	0 Cu. yds @	\$1.08 /cu. yd =		\$0
Cost / Hour =	\$77.00	Riprap	0 Cu. yds @	\$1.08 /cu. yd =		\$0
CY / Load =	20					

Rock total = \$0

IV. CULVERTS AND FLUMES:

Description	Qty.	Gauge na	Diameter (in.)	No/Length (ft)	Installed Cost/ft	Sub-total
	0		18	36	\$11.80	\$0

Bands & Gaskets 3 - 18"@ \$9.90ea \$0

Culvert total = \$0

V. STRUCTURES

Description	Type	Width	Length	Cost/ft.	Sub-total
					\$0
					\$0
					\$0

Structure total = \$0

Sub-TOTAL = \$3,191

VI. GENERAL EXPENSES:

Overhead & General Exp. Add 12% \$383

VII. MOBILIZATION:

Description	\$ per Move	# of Moves	Sub-total
Dump Trucks	100	0	\$300
Grader	400	1	\$400
0	0	0	\$0
Excavator	450	0	\$450
0	0	0	\$0
0	0	0	\$0
0	\$0	0	\$0
0	\$0	0	\$0

Total Mobilization = \$1,150 Mobilization sub-total = \$575

Road No. 0
Standard: Secondary Mainline (12' R.S.)
Stations: 0.00

SHEET TOTAL = \$4,149

By: Hanlin

Sheet 4 of 4

Date: 03/04/04